ABBREVIATIONS

DEGREE	°
POUND OR NUMBER	#
AND	&
AT	@
A	
ANCHOR BOLT	A.B.
ABOVE FINISH FLOOR	A.F.F.
ACOUSTICAL CEILING FINISH	ACF.
ACOUSTICAL TILE CEILING	ATC
ACOUSTICAL WALL COVERING	AWC
ADJUSTABLE	ADJ.
AIR CONDITIONING	AC.
AIR HANDLING UNIT	AHU
ALLOY	ALY.
ALTERNATE	ALT.
ALUMINUM	ALUM.
ANCHOR	ANCH.
ANCHOR BOLT	A.B.
APPLIED GLUE	ADLT
LAMINATED TIMBER	
APPROXIMATE(LY)	APPROX.
ARCHITECTURAL)	ARCH.
AREA DRAIN	A.D.
ASPHALT	ASPH.
AT	@
B	
BACK TO BACK	B/B
BACK OF CURB	B.C.
BASE BID	B.B.
BASEMENT	BSMT.
BEAM	BM.
BEARING	BRG.
BENCHMARK	BMK.
BLOCKING	BLKG.
BOARD	BD.
BOTTOM	BOT.
BOTTOM OF	B.O.
BOTTOM OF CURB	B.O.C.
BOTTOM OF STAIRS	BS.
BOTTOM OF WALL	B.O.W.
BRICK EXPANSION JOINT	B.E.J.
BUILDING	BLDG.
BUILDING LINE	B.L.
C	
CABINET UNIT HEATER	CUH.
CANTILEVER	CANT.
CARPET	CPT.
CAST IN PLACE	CIP
CAST IRON	CI.
CATCH BASIN	C.B.
CEILING	CLG.
CEILING	CLG.
CEMENT	CEM.
CEMENT PLASTER	CEM. PL.
CENTER	CENT.
CENTER LINE	CL.
CENTER TO CENTER	C/C
CERAMIC TILE	CT
CHALKBOARD	CB
CLEAN OUT	C.O.
CLEAR	CLR
CLEAR FLOAT GLASS	CFG
CLEAR TEMPERED GLASS	CTG
CLEAR TEMPERED	
INSULATED GLASS	CTIG
CLEAR MIRROR GLASS	CMG
CLOSET	CLOS.
COLUMN	COL.
COMPRESSIBLE	COMP.
CONCRETE	CONC.
CONCRETE MASONRY UNIT	CMU
CONCRETE PIPE	CP.
CONCRETE	CONC.
CONNECTION	CONN.
CONSTRUCTION	CONST.
CONTINUOUS	CONT.
CONTRACTOR	CONTR.
CONTROL JOINT	C.J.
COVER ELEVATION OF AREA INLET (INLET ELEV.)	C.E.
CORNER GUARD	C.G.
CORRIDOR	CORR.
CORRUGATED METAL PIPE	CMP
CUBICLE CURTAIN TRACK	C.C.T.
D	
DEAD LOAD	D.L.
DEEP	D.
DETAIL	DET.
DIAGONAL	DIAG.
DIAMETER	DIA. Ø
DIMENSION	DIM.
DISPENSER	DISP.
DOOR	DR.
DOWN	DN.
DOWNSPOUT	D.S.
DRAIN TILE	DT
DRAWING	DWG.
DRINKING FOUNTAIN	DF
E	
EACH	EA.
EACH FACE	E.F.
EACH WAY	EW
ELECTRIC(AL)	ELEC.
ELECTRIC WATER COOLER	EWC
ELEVATION	ELEV.
ELEVATOR	ELEV.
EQUAL	EQ.
EQUIPMENT	EQUIP.
EXCAVATE	EXC.
EXISTING	EXIST. OR EXG.
EXISTING ROOF DRAIN	E.R.D.
EXPANSION JOINT	EJ
EXPANSION JOINT COVER	E.J.C.
EXPOSED	EXP.
EXTERIOR	EXT.
F	
FABRIC WALL COVERING	FWC
FEET	FT.
FINISH	FIN.
FINISHED FLOOR	F.F.
FINISH FLOOR ELEVATION	F.F.E.
FIRE ALARM	F.A.
FIRE EXTINGUISHER	F.E.
FIRE EXTINGUISHER CABINET	F.E.C.
FIRE HOSE CABINET	F.H.C.
FIRE HYDRANT	FH
FIREPROOF(ING)	FRPF.
FIRE RATED GLASS CERAMIC	FRGC
FIRE RATED, SAFETY RATED GLASS CERAMIC	FRSRGC
FLASHING	FLASH'G
FLEXIBLE	FLEX.
FLOOR	FL.
FLOOR DRAIN	FD
FLOORING	FLG.
FLOW LINE	
FLUSH CEMENT	FLUOR.
FOLDING PANEL PARTITION	FP
FOOTING	FTG.
FOUNDATION	FDN.
FRAME	FR.
FURR'G	FUR'G
FIELD VERIFY	F.V.
FIXTURE	FIXT.
G	
GALVANIZED	GALV.
GAUGE	GA.
GLASS FIBER REINFORCED GYPSUM	G.F.R.G.
GLU-LAM BEAM	G.L.B.
GRAB BAR	GB
GRADE	GR
GRAIN	GRAN.
GROUND FACE CONCRETE MASONRY UNIT	GFCMU
GUTTER	G.
GYPSUM WALLBOARD	GWB
GYPSUM	GYP.
H	
HAND DRYER	H.D.
HANDICAPPED	HC
HARDWARE	HDWE.
HARDWOOD	HDWD.
HEIGHT	HT.
HEAVY CLEAR TEMPERED GLASS	HCTG
HIGH	H.
HIGH POINT	HP.
HOLLOW CORE	HC
HOLLOW METAL	H.M.
HORIZONTAL	HORIZ.
HOUR	HR.
I	
INCH	IN.
INFORMATION	INFO.
INSIDE DIAMETER	I.D.
INSIDE FACE	I.F.
INSULATION	INSUL.
INTERIOR	INT.
INTERIOR DIAMETER	I.D.
INVERT ELEVATION	I.E.
INSULATED TRANSLUCENT PANEL SYSTEM	I.T.P.S.
J	
JANITOR	JAN.
JOINT	JT.
JOIST	JST.
JOIST BEARING	JST. BRG.
K	
KEYBOARD TRAY	K.B.
KEYED CONSTRUCTION JOINT	K.C.J.
KITCHEN	KIT.
L	
ANGLE	L OR ⧋
LANDSCAPE ARCHITECT	LA
LAVATORY	LAV.
LIGHT	LT.
LIGHT WEIGHT	LT. WT.
LINEAL FOOT	L.F.
LINEAR FOOT	L.F.
LIVE LOAD	L.L.
LOCATION	LOC.
LONG LEG HORIZONTAL	L.L.H.
LONG LEG VERTICAL	L.L.V.
LOW POINT	LP
M	
MANAGEMENT	MGMT.
MANHOLE	M.H.
MANUFACTURER	MANF.
MARKERBOARD	M.B.
MASONRY	MAS.
MASONRY OPENING	M.O.
MATERIAL	MATL.
MAXIMUM	MAX.
MECHANICAL	MECH.
METAL	MTL.
MINIMUM	MIN.
MIRROR	MR
MISCELLANEOUS	MISC.
MOP/BROOM HOLDER	M.B.H.
MOUNT	MT.
MOUNTED	MTD.
MULLION	MULL.
N	
NAPKIN DISPENSER	ND.
NAPKIN DISPOSAL	NDL.
NOMINAL	NOM.
NOT IN CONTRACT	NIC
NOT TO SCALE	NTS
NUMBER	NO.
O	
OCCURRING	OCCURG
OFFICE	OFF.
ON CENTER(S)	O.C.
ON CENTER EACH WAY	O.C.E.W.
ON CENTER	OC
OPENING	OPNG.
OPPOSITE	OPP.
OUTSIDE DIAMETER	O.D.
OUTSIDE FACE	O.F.
OVERFLOW DRAIN	O.D.
OVERHEAD	OVHD
P	
PAINT	P.
PAIR	PR.
PANEL	PNL.
PAPER HOLDER	PH.
PAPER TOWEL DISPENSER	P.T.D.
PAPER TOWEL RECEPTACLE	P.T.R.
PARTITION	PTN.
PAVEMENT	PVMT
PERIMETER	PERIM.
PLATE	PL. or P.
PLASTER	PLAS.
PLASTIC LAMINATE	PLAM.
PLYWOOD	PLYWD.
POLISHED	POL.
POLYVINYL CHLORIDE	PVC
PORCELAIN TILE	PORC.
PRECAST CONCRETE	P.C.
PREFINISHED	PF
PROJECT(ION)	PROJ.
PROPERTY	PROP.
Q	
QUARRY TILE	Q.T.
R	
RADIUS	R.
RADIUS POINT	RP
RECESSED	REC.
REFERENCE	REF.
REFRIGERATOR	REFR
REINFORCING	REINF.
REMOVE	REM.
REQUIRED	REQ'D.
RETURN AIR	RA
RETAINING	RET.
REVERSE	REV.
RIGHT-OF-WAY	R.O.W.
RIM ELEVATION	RE
RISER	R.
ROOF DRAIN	RD
ROOF TOP UNIT	RTU
ROOF HATCH	R.H.
ROOM	RM.
ROUGH OPENING	R.O.
RUBBER	RUB.
S	
SANITARY SEWER	SAN.
SAW JOINT	S.J.
SCHEDULE	SCHED.
SEALANT	SEAL.
SECTION	SECT.
SERVICE	SERV.
SHEET VINYL	S.V.
SHEATHING	SHTHG
SHEET	SHT.
SHEET METAL	S.M.
SHEET VINYL	S.V.
SIMILAR	SIM.
SLAB-ON-GRADE	S.O.G.
SOAP DISPENSER	SD
SOLID CORE	S.C.
SPACE	SP.
SPECIFICATIONS	SPEC.
SPACED	SPACD.
SQUARE	SQ.
SQUARE FEET	S.F.
STAGGERED	STAGD.
STAIR	ST
STAINLESS STEEL	S.S.
STANDARD	STD.
STEEL	STL.
STORAGE	STOR.
STRUCTURE(AL)	STRUCT.
STRUCTURAL GLAZED FACING TILE	S.G.F.T.
SUPPLY AIR	S.A.
SURFACE	SURF.
SUSPENDED	SUSP.
SYMETRICAL	SYM.
T	
TACKBOARD	TB
TACK WALL	T.W.
TELEPHONE	TEL., TELE
TELEVISION	TV.
TEMPERATURE	TEMP.
TERRAZZO	TERR.
THICK	T.
THICK	THK
THRESHOLD	THR.
THROUGH WALL FLASHING	T.W.F.
THRU	THRU
TINTED INSULATING GLASS	TIG
TINTED TEMPERED INSULATING GLASS	TTIG
TINTED TEMPERED GLASS	TTG
TINTED TEMPERED LAMINATED INSULATING GLASS	TTLIG
TOE OF SLOPE	TOE
TOILET	T.
TOILET PAPER DISPENSER	T.P.D.
TONGUE & GROOVE	T & G
TOP OF	T.O.
TOP OF CURB	T.O.C.
TOP OF FOOTING	T.O.F.
TOP OF SLOPE	TOE
TOP OF STAIRS	TS
TOP OF STEEL	T.O.S.
TOP OF WALL	TW.
TOPOGRAPHY	TOPO.
TOWEL	TWL.
TOWEL DISPENSER	TD
TOWEL DISPENSER/DISPOSAL	TDDL
TREAD	T.
TUBE STEEL	T.S.
TYPICAL	TYP.
U	
UNDERGROUND	UG
UNDERGROUND ELECTRICAL	UGE
UNDERGROUND TELEPHONE	UGT
UNIT HEATER	UH
UNLESS NOTED OTHERWISE	U.N.O.
UPPER LEVEL	U.L.
URINAL	UR.
UTILITY	UTIL.
V	
VERTICAL	VERT.
VESTIBULE	VEST.
VINYL	VIN.
VINYL ASBESTOS TILE	VAT
VINYL BASE	VB
VINYL COMPOSITION TILE	VCT
VINYL WALL COVERING	VWC
VISUAL DISPLAY BOARD	V.D.B.
W	
WAINSCOT	WSCT.
WALLCOVERING	WC.
WALL HYDRANT	WH
WALL PROTECTION PANEL	WPP
WASTE RECEPTACLE	WR
WATER CLOSET	W.C.
WATT	WT.
WELDED WIRE FABRIC	WWF
WIDE FLANGE	WF.
WIDE	W.
WINDOW	WIN.
WITH	W/
WITHOUT	W/O
WIRE GLASS	WG
WOOD	WD.
WOOD BASE	WB
WORKING POINT	WP
Y	
YARD	YD.
YARD HYDRANT	Y.H.

MATERIALS

EARTH	DIMENSION LUMBER	CERAMIC OR QUARRY TILE	
GRANULAR FILL	PLYWOOD	TERRAZZO	
CONCRETE	FINISH WOOD	ACOUSTICAL TILE	
CONCRETE MASONRY	PARTICLE BOARD	CARPET	
BRICK	ROOF OR RIGID INSULATION	TERRAZZO	
CUT STONE	CAULKING OR SEALANT		
COMPRESSIBLE FILLER	BATT OR LOOSE INSULATION		
STEEL	GYPSUM BOARD OR PLASTER		

REFERENCE SYMBOLS

DETAIL — 10 / A-1 — Detail number; Sheet where detail is found

ELEVATION — 10 / A-1 — Detail number; Sheet where detail is found; A / 10 / A-1 / B

WALL SECTION REFERENCE — 1 / A3-3

BUILDING SECTION REFERENCE — 1 / A3-3

DOOR OPENING AND TAG — # / #

COLUMN LINES — NEW / B.2

WALL TYPES — 2

ROOM NAME AND NUMBER — CLASSROOM / 100

NORTH ARROW

HEIGHT ELEVATION — 8'-0" A.F.F. / T.O. WALL

WINDOW TAG — 11

TYPICAL WALL TYPE SCHEDULE

MTL. STUDS TYPE	MTL. STUDS DESCRIPTION	MASONRY TYPE	MASONRY DESCRIPTION
5.1 / 5.1A	5/8" GWB; 3 5/8" MTL. STUDS; SOUND INSUL. AT TYPE 5.1A; 4⅛"	8	8" CMU; 7⅝"
5.2 / 5.2A	5/8" GWB EACH SIDE; 3 5/8" MTL. STUDS; SOUND INSUL. AT TYPE 5.2A; 4⅛"		
5.4 / 5.4A	2 LAYERS 5/8" GWB EACH SIDE; 3 5/8" MTL. STUDS; SOUND INSUL. AT TYPE 5.2A; 6⅛"		
7.1 / 7.1A	5/8" GWB; 6" MTL. STUDS; SOUND INSUL. AT TYPE 7.1A; 6⅛"		
7.2 / 7.2A	5/8" GWB EACH SIDE; 6" MTL. STUDS; SOUND INSUL. AT TYPE 7.2A; 7⅛"		

WALL TYPE NOTES:

1. WHERE WALL TYPE INDICATES DIFFERENT 2 OF LAYERS OF GWB ON ONE SIDE AND ONE LAYER ON THE OTHER SIDE, THE SIDE OF THE WALL THAT THE SYMBOL POINTS TO RECEIVES THE TWO LAYERS OF GWB.

GENERAL NOTES

1. All Contractors shall review Contract Requirements and Procedures outlined in the Specifications. The work outlined in the Drawings and Specifications shall be incorporated into the General Contract. The Construction Manager shall be responsible for all materials, methods and means required to execute the General Contract and provide a finished product.
2. Verify Mechanical and Electrical conditions for scope and interface. Contractor shall coordinate location for all mechanical and electrical items with general construction. Review any discrepancies with Architect prior to installation and/or fabrication.
3. Protect all site locations that are not designated for removal. Any damage caused by the Contractor's operations shall be repaired at the Contractor's expense.
4. All dimensions are to face of finished wall, unless noted otherwise. Review placement of walls with details and furnishings, casework or mechanical and electrical items. Review any discrepancies with Architect prior to construction and/or fabrication. All dimensions are for bidding purposes only. Actual field dimensions shall be verified prior to submitting shop drawings, ordering related materials, demolition or construction.
5. Extend all studs, gypsum wallboard (GWB) and acoustical batts to structure, unless otherwise noted or detailed.
6. Provide wood blocking behind all wall stops, finish trim, building hardware and toilet accessories to be mounted on walls. Provide continuous wood blocking horizontally and vertically, behind all wall hung equipment, accessories, counters and any other building materials requiring anchoring to walls, ceilings and floors. Verify with all trades for these items prior to covering the structure.
7. Areas noted as N.I.C. are not in contract.
8. Construction Manager shall contact the Architect in the event that unforeseen conditions are encountered.
9. All gypsum wallboard (GWB) noted or scheduled on the Drawings shall be suspended and/or supported with framing in accordance with industry standards where not specifically detailed or specified.
10. All metal studs are 3 5/8" unless noted otherwise.
11. All materials shall be new unless specifically noted otherwise.
12. All mechanical openings and other openings or penetrations through rated walls shall be sealed to maintain ratings.
13. All work shall comply with applicable codes, regulations, and ordinances.
14. All studs shall be held at least 1/4" away from structural steel columns.
15. See structural for control joints at interior slabs-on-grade.
16. In some instances, thermal and sound batt insulation has been omitted from the details for clarity. See wall types for location of insulation.
17. If instances arise during construction of this project that require penetrations of structural members due to methods of routing ducts, pipes, etc. different from routing shown on the drawings, costs for penetration of structural members shall be born by the contractor requiring the penetration. Before penetration through a structural member can be made, the contractor shall inform the Architect of his/her intent and shall await instructions from the Architect as to exact placement of, and details for, such penetrations.
18. Where vinyl wall covering occurs at an interior control joint, tuck vinyl wall covering into joint.
19. Hardwood is to be Maple unless noted otherwise.
20. At exterior walls, provide mold resistant gypsum wallboard.
21. All ceiling heights listed in room finish schedule are from the finish floor of the listed room unless noted otherwise.
22. All angles on plan are 90 degrees or 45 degrees unless noted otherwise.
23. At the large scale column plan details, wall types are indicated. For clarity, in some instances, not all studs and/or furring are shown on the detail. Contractor shall frame using normal framing methods and shall also comply with those outlined in the specifications.
24. Contractor shall visit the site and review conditions prior to bidding.
25. Contractor shall field verify all site conditions for workability, adjacent conditions, effects and accessibility. All dimensions are for bidding purposes only. Contractor shall field verify dimensions prior to ordering related materials of construction.



1 CONTROL JOINT DETAIL
1" = 1'-0"

ROBERT J. MABREY REGISTERED NO. 5683 COMMONWEALTH OF KENTUCKY ARCHITECT

REVISIONS

no.	description	by	date

CONSTRUCTION DOCUMENTS

HOLY SPIRIT CATHOLIC CHURCH

4754 SMALLHOUSE ROAD, BOWLING GREEN, KENTUCKY
BERINGER CIACCIO DENNELL MABREY - ARCHITECTURE, LANDSCAPE ARCHITECTURE, INTERIOR DESIGN, CONSTRUCTION MANAGEMENT

bccm — OMAHA ■ DES MOINES

A0-0

26 NOVEMBER 2008
BCCM NO. 0364-06